

2. The project proponent should submit copy of Environmental Clearance to the Heads of Local bodies, Panchayats and Municipal bodies in addition to relevant offices of Government who in turn has to display the same for 30 days from the date of receipt. The clearance letter shall also be put on the website of the Company by the proponent.
3. The environmental safeguards and monitoring schedule as contained in the EMP should be implemented in letter and spirit & there will be no departure from the final project proposal as approval herein.
4. Officials from Regional Office, Ministry of Environment, Forests & Climate Change, Govt. of India/ State Level Environment Impact Assessment Authority / Delhi Pollution Control Committee, who would be monitoring the implementation of environmental safeguards, should be given full cooperation, facilities and documents/data on site by the project proponents during their site inspection.
5. A complete set of all the documents submitted to SEAC should be forwarded to Regional Office, Ministry of Environment, Forests & Climate Change, Govt. of India and Delhi Pollution Control Committee.
6. In the case of any change(s) in the scope of the project, the project would require a fresh appraisal by the SEAC and approval of SEIAA.
7. The project proponent shall comply with the notifications and court orders issued time to time regarding use, sale and storage of all kinds of plastic bags.
8. E-waste generated in the complex should be managed as per CPCB guidelines on E-waste management and disposed through approved e-waste recyclers.
9. Hazardous waste should be disposed off as per Rules applicable.
10. The solid waste (dry as well as wet garbage) generated should be properly collected and segregated before disposal to Municipal Authorities in accordance with the Municipal Solid Waste (Management & Handling) Rules, 2000. No municipal waste should be disposed off outside the premises. Adequate measures should be taken to prevent odour problem.
11. State Environmental Impact Assessment Authority reserves the right to add additional safeguard measures subsequently, if found necessary, and to take action including the revoking of the environmental clearance under the provisions of the Environmental (Protection) Act, 1986, to ensure effective implementation of the suggested safeguard measures in a time bound and satisfactory manner.



2. The ground water drawl from existing/proposed bore well during construction and operation phase should be done only with the prior permission of DJB. The ground water level and its quality should also be monitored regularly.
3. The position / location of the DG Sets & other Utilities etc. installed by the project proponent as per the provisions made in the layout plan, should not be changed later-on under any circumstances.
4. Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control and for water conservation.
5. Utilization of Diesel power generating sets is subject to power failure condition only. The DG sets proposed as a source of power back up during operation phase should be of enclosed type, low sulphur diesel run and conform to rules made under the Environment (Protection) Act, 1986. The DG sets should be subjected to periodic noise and stack monitoring. Waste/used diesel should be stored and managed as per Hazardous Waste (Management and Handling) Rules, 2000 as amended to date and be sold to CPCB approved recyclers.
6. Noise should be controlled to ensure that it does not exceed the prescribed standards. During night time the noise levels measured at the boundary of the building shall be restricted to the permissible levels to comply with the prevalent regulations.
7. Energy Conservation measures such as solar lighting for common areas, LEDs for lighting of areas, signage, solar inverters etc should be adopted.
8. Used CFLs/ LEDs should be properly collected and disposed off/ sent for recycling as per the prevailing guidelines/rules of the regulatory authority.
9. Thick green belt of the adequate width and density with local species, as per plan submitted, shall be raised along the periphery of the plot so as to provide protection against particulates and noise. The open spaces inside the plot should be suitably landscaped and covered with vegetation of indigenous species/variety.
10. Traffic congestion near the entry and exit points from the roads adjoining the project site must be avoided. Parking should be fully internalized and no public space should be utilized.



12. Environmental clearance is subject to final order of the Hon'ble Supreme Court of India in the matter of Goa Foundation Vs. Union of India in Writ Petition (Civil) No. 460 of 2004 as may be applicable to this project and decisions of any Competent Court, to the extent applicable.
13. All other statutory clearances such as the approvals for storage of diesel from Chief Controller of Explosives, Fire Department, Civil Aviation Department etc. shall be obtained, as applicable by project proponents from the respective competent authorities.
14. These stipulations would be enforced among others under the provisions of Water (Prevention and Control) Pollution Act, 1974, the Air (Prevention and Control) Act 1981, the Environment (Protection) Act, 1986, the Public Liability (Insurance) Act, 1991 and EIA Notification, 2006.
15. Status of compliance to the various stipulated environmental conditions and environmental safeguards will be uploaded by the project proponent in its website.
16. The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard & soft copies) to Regional Office, Ministry of Environment, Forests & Climate Change, Govt. of India, SEIAA-Delhi and Delhi Pollution Control Committee.
17. This environmental clearance will be valid for a period of Seven years from the date of its issue.
18. It will be the responsibility of the project proponent to obtain prior clearances/approval & ensure compliances under all other relevant Acts/ Rules/ Regulations/ guidelines/ instructions/Court Orders/Tribunal Orders as applicable to this project before starting of the project.
19. In view of MoEF&CC Office Memorandum No. 21-270/2008-IA.III dated 19.06.2013 read with MoEF&CC Office Memorandum No. 22-154/2015-IA.III dated 10.11.2015, this environmental clearance is being granted focusing only on the environment concerns. The project will be regulated by the concerned local Civic Authorities under the provisions of the relevant provisions of the extant MPD-2021, Building Control Regulations and Safety Regulations.
20. This Environmental Clearance is subject to the condition that concerned local civic agencies will give the permission for use/ occupation of the building only after the written assurance of DJB/ New Delhi Municipal Council / other such local civic authority (as the case may be) regarding supply of adequate water for the residents/ occupiers.



existing Ground Coverage is 2429.118 sq.mt and the proposed Ground Coverage is 418.92 sq.mt. The total Ground Coverage is 2848.038 sq.mt. The permissible FAR area is 19710.659 sq.mt. The existing FAR area is 16699.801 sq.mt and the proposed FAR area is 2979.58 sq.mt. The total FAR area is 19679.381 sq.mt. The total stilt area is 2848.038 sq.mt (existing: 2429.118 sq.mt. + proposed: 418.92 sq.mt.). The total number of dwelling units is 166. The maximum number of floors will be Stilt+7. The total number of blocks is 3. The maximum height of building is 29.95 m. The existing parking provision is for 209 ECS and the proposed parking provision is for 80 ECS. The total parking provision is for 289 ECS (206 ECS in open + 83 ECS in stilt). The total estimated population after proposed expansion is 913 (residential: 830 persons + visitors: 83 persons). The total proposed green area is 2335.817 sq.mt (19.79 % of plot area). The total number trees will be 155. The total water requirement will be 120.3 KLD (113.3 KLD: Domestic, 7 KLD: Horticulture). The source of water supply will be Municipal water supply. 98 KLD of waste water generated from the society will be treated in the Dwarka CSTP. The Rain Water Harvesting Pits at present are 2 in number. The total municipal solid waste generation after proposed expansion will be 278.55 kg/day. The existing power requirement is 2195 KW. The power supply is met from BSES. DG set of 1x 200 KVA is proposed for power backup. Cost of the project is 2 Crores.

The requirements of the project have been taken into account by SEAC during the appraisal of project. The SEIAA took account of the discussions and environmental conditions imposed during the consideration of the project in the SEAC meetings held on 05.04.2013, 23.05.2013, 21.07.2014, 28.07.2015, 26.09.2015, 17.10.2015 and 12.12.2015.

The State Level Environment Impact Assessment Authority, Delhi (SEIAA-Delhi) in its 29th meeting held on 11.02.2016 hereby accords the Environmental Clearance to the above said project as per provisions of Environment Impact Assessment Notification, 2006 and its subsequent amendments, subject to the strict compliance of the terms and conditions as follows:



competent authority. The Rules on the Solid Waste Management including Construction waste issued by MoEF&CC as amended will be applicable.

4. Construction spoils, including bituminous material and other hazardous materials, must not be allowed to contaminate watercourses and the dump sites for such material must be secured so that they should not leach into the ground water.
5. Any hazardous waste generated during construction and operation phase should be disposed off as per applicable rules and norms with necessary approvals to the Delhi Pollution Control Committee.
6. Proper measures should be adopted to control dust emissions during construction phase.
7. Vehicles hired for bringing construction material to the site and other machinery to be used during construction should be in good condition and should have a pollution check certificate and should conform to applicable air and noise emission standards and should be operated only during non-peak hours. The material loaded or unloaded should be covered (especially sand, excavated soil) before transportation to avoid fugitive emissions etc.
8. Techniques like, air extraction equipment, and covering scaffolding, hosing down road surfaces, reducing the speed of vehicle, use of covering sheets for vehicles carrying construction materials and cleaning of vehicles to reduce dust and vapour emissions. Measures should include appropriate containment around bulk storage tanks and materials stores to prevent spillages entering watercourses.
9. The Diesel Generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environment Protection Rules prescribed for air and noise emission standards.
10. The diesel required for operating DG sets shall be stored in underground tanks and if required, clearance from Chief Controller of Explosives shall be taken.
11. Ambient noise levels should conform to prescribed standards both during day and night. Adequate measures should be made to reduce ambient air and noise level during construction and operation phase, so as to conform to the norms stipulated by CPCB/DPCC. Ambient air and noise monitoring should be done by an accredited lab and data should also be submitted, on six monthly bases, with DPCC& Regional Office of MoEF&CC. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase.



7. Solar Photovoltaic (SPV) system should be installed to reduce use of conventional source of energy. Minimum 50% of roof top area of building should be utilized for installation of Solar Panels/ SPV system.
8. Total capacity of DG sets should not exceed 30% of the total load.
9. Biodegradable waste should be converted into compost.
10. No extra power load should be sanctioned.
11. Construction & Demolition waste should be disposed of at authorized C&D waste processing unit.
12. Minimum 8 m high barricade should be provided all around the project site before the start of construction.
13. During the construction Phase for control of dust pollution all precautionary measure should be ensured in compliance of Hon'ble National Green Tribunal order dated 4.12.2014 & 10.04.2015 in O.A. No.21 of 2014 and O.A. No. 95 of 2014 in the matter of Vardhaman Kaushik Vs. Union of India & others and Sanjay Kulshreshtha Vs Union of India &ors.
14. Environmental Clearance was granted to the project in view of the DDA's letter No. 23(15)/99/Bldg./538 dated 04.12.2014, with the condition that grant of Environmental Clearance will not be construed or taken as the excuse for structural safety & other construction related issues. The decision on structural safety and the applicability of order dated 16.04.2012 issued by Director (Planning), DDA on utilization of additional FAR, without compromising structural safety, shall be decided by DDA/ MCD independently while giving necessary approvals.

PART B – GENERAL CONDITIONS:

1. The project proponent should prominently advertise in at least two local Newspapers widely circulated in the region indicating that the project has been accorded Environmental Clearance and copy of clearance is available with the DPCC and may also be seen on the website of DPCC at <http://www.dpcc.delhigovt@nic.in>. The advertisement should be made within 10 days from the date of receipt of the Clearance letter and a copy of the same should be forwarded to the Regional Office of MoEF&CC and SEIAA-Delhi.

PART A – SPECIFIC CONDITIONS:

I. PRE-CONSTRUCTION PHASE

1. Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.
2. The Project Proponent shall obtain all other necessary requisite clearances/ permissions from concerned authorities/ agencies before commencement of work.
3. A first aid room to be provided in the project both during construction and operation phase of the project.
4. The Approval of competent authority shall be obtained for structural safety of the building due to earthquake, adequacy for fire fighting equipments etc as per National Building Code including protection measures from lightening etc.
5. All required sanitary and hygienic measures should be in place before starting construction activities and to be maintained throughout the construction phase.
6. Provision shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile STP, safe drinking water, medical health care, crèche etc. The housing may be in the form of temporary structures to be removed after completion of the project.

II. CONSTRUCTION PHASE:

1. The Project Proponent shall ensure that the guidelines issued by Ministry of Environment, Forests & Climate Change (MoEF&CC), vide OM No. 19-2/2013-IA.III dated 09.06.2015, to be followed for building and construction projects to ensure sustainable environmental management in pursuance of Notification No. 3252 (E) dated 22. 12.2014 under the EIA Notification, 2006, as applicable, are followed in this project.
2. All the top soil excavated during construction activities should be stored for horticulture/landscape development within the project site.
3. Disposal of muck during construction phase should not create any adverse effect on the neighbouring communities and be disposed off after taking the necessary precautions for general safety and health aspects of people, only in approved sites with the approval of



IV. ENTIRE LIFE:


1. The project proponent will be responsible for the operation, maintenance and implementation of environmental safeguards for the project.
2. The ground water drawl from existing/proposed bore well should be done only with the prior permission of DJB.
3. Rainwater harvesting system shall be properly maintained and kept functional and periodical cleaning of the same shall be undertaken specifically including the period before onset of the monsoon.
4. Incremental pollution loads on the ambient air quality, noise, stack and water quality should be periodically monitored.
5. Thick green belt of the adequate width and density with local species, as per plan submitted, shall be maintained.
6. Traffic congestion near the entry and exit points from the roads adjoining the project site must be avoided. Parking should be fully internalized and no public space should be utilized.

V. OTHER SPECIFIC CONDITIONS:

1. Sewerage discharge from the project shall be continued to be discharged in DJB sewer for treatment in STP of the area.
2. The Project Proponent shall procure the treated waste water from nearby DJB STP for reuse in horticulture etc.
3. The Rain Water Harvesting pits with oil & grease trap with settling tank will be maintained and regular clean up will be taken up.
4. Project Proponent shall ensure that Solid waste generation from the Project will be collected and segregated at source and shall be disposed as per MSW, 2000 Rule & guidelines.
5. Ground water should be extracted only after the permission from DJB.
6. Minimum 1 tree for every 80 Sq. Mt of plot area should be planted within the project site in accordance with the landscape plan submitted.



21. Grant of environmental clearance does not necessarily implies that water/ power supply shall be granted to the project and that their proposals for water/ power supply shall be considered by the respective authorities on their merits and decision taking.
22. The investment made in the project, if any, based on environmental clearance so granted, in anticipation of the clearance from water/ power supply angle shall be entirely at the cost and risk of the project proponent and SEIAA, Delhi shall not be responsible in this regard in any manner.
23. This Environmental Clearance is subject to the condition that concerned local civic agencies will give the permission for use/ occupation of the building only after the written assurance of DJB/ New Delhi Municipal Council / other such local civic authority (as the case may be) regarding supply of adequate water for the residents/ occupiers.
24. Grant of environmental clearance does not necessarily implies that water/ power supply shall be granted to the project and that their proposals for water/ power supply shall be considered by the respective authorities on their merits and decision taking.
25. The investment made in the project, if any, based on environmental clearance so granted, in anticipation of the clearance from water/ power supply angle shall be entirely at the cost and risk of the project proponent and SEIAA, Delhi shall not be responsible in this regard in any manner.
26. Any appeal against this clearance shall lie with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.


(H. S. Sohal)
Member Secretary
SEIAA-Delhi

Copy to:

1. Sh. Krishan Mohan Sahni, Chairman, State Level Environment Impact Assessment Authority-Delhi, 38, Pocket-2, Jasola Vihar, New Delhi.
2. The Secretary(Environment)-cum-Chairman(DPCC), Department of Environment, Govt. of NCT Delhi, Secretariat Building, 6th Level, C-Wing, I.P.Estate, New Delhi-02.
3. The Additional Principal Chief Conservator of Forests (C), Regional Office (Central), Ministry of Environment, Forests & Climate Change, Govt. of India, Kendriya Bhawan, 5th Floor, Sector-H, Aliganj, Lucknow-226024, Uttar Pradesh.

4. The Director, Impact Assessment Division, Monitoring Cell, Ministry of Environment, Forests & Climate Change, Govt. of India, Indira Paryavaran Bhawan, Jorbagh, New Delhi-110003.
5. SEE (IT)- for necessary action regarding uploading the EC on website.

Handwritten signature and date
13/16

(H. S. Sohal)
Member Secretary
SEIAA-Delhi

**STATE ENVIRONMENTAL IMPACT ASSESSMENT AUTHORITY
(SEIAA)-DELHI**

OFFICE OF DELHI POLLUTION CONTROL COMMITTEE
5th Floor, ISBT Building, Kashmere Gate, Delhi-110006
visit us at : <http://dpcc.delhigovt.nic.in>

F.No. DPCC/ SEIAA-D-III/C166/ 2016/ **3158-3163**

Dated: **01/03/2016**

Environmental Clearance No.: SEIAA-D/ C166/EC-316/2016

To,

Col RC Kapoor, Retd., Secretary,
DIN Cooperative Group Housing Society (CGHS) Ltd.,
Plot no. 7, Sector-4, Dwarka, Phase-I,
New Delhi-110078.

Sub: Environmental Clearance for "Proposed Expansion of Balconies of DIN CGHS Ltd., at Plot No. 7, Sector-4, Dwarka, Phase-I, New Delhi-110078."

This has reference to your application submitted on 04.03.2013 for seeking Environmental Clearance under Environmental Impact Assessment Notification dated 14.09.2006 amended as on date for "Proposed Expansion of Balconies of DIN CGHS Ltd", at Plot No. 7, Sector-4, Dwarka, Phase-I, New Delhi-110078 and subsequent presentation given before the State Level Expert Appraisal Committee (SEAC) for seeking prior environmental clearance for subject cited project as required under the EIA Notification, 2006. The proposal has been appraised in the meetings of SEAC as per procedure prescribed under the provisions of EIA Notification dated 14.09.2006 on the basis of the documents submitted with the application viz., Form-1, 1-A, conceptual plan and the additional clarifications furnished in response to the observations of the State Level Expert Appraisal Committee.

It is inter-alia noted that the proposal is for the grant of Environmental Clearance for Proposed Expansion of Balconies of DIN CGHS Ltd., at Plot No. 7, Sector-4, Dwarka, Phase-I, New Delhi-110078. The total plot area is 11802.79 sq.mt. The existing built-up area is 19447.285 sq.mt and the proposed built-up area for expansion is 3398.5 sq.mt. The total built-up area is 22845.785 sq.mt. The permissible Ground Coverage is 3933.869 sq.mt (33.33 % of the plot area). The

12. Fly ash should be used as building material in the construction as per the provisions of Fly Ash Notification of September, 1999 and amended as on 27th August, 2003.
13. Ready Mix Concrete must be used in building construction.
14. Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices preferred.
15. Proponent shall obtain prior permission for ground water withdrawal from Delhi Jan Board, in compliance of notification dated 12.07.2010.
16. Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.
17. Construction/provision of the DG Sets, Utilities etc, earmarked by the project proponent on the layout plan, should be made in the earmarked area only. In any case the position/location of these utilities should not be changed later-on.
18. Health and safety norms of CPWD should be followed during construction.
19. Soil and water samples of the site should be tested by the proponent through DPCC recognized laboratory to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants, on quarterly basis for inclusion in the six monthly report.
20. Adequate steps shall be taken to conserve energy by limiting the use of glass up-to 40% to reduce the electricity consumption and load on air-conditioning. If necessary, use high quality double glass with special reflective coating in windows, provision of proper thermal insulation and taking measures as prescribed under the Energy Conservation Building Code.
21. Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to all surroundings.
22. Treated water of DJB STP should be used for construction purposes upto the maximum extent possible.
23. Packaged/ mobile STP shall be provided for labour camp during construction phase.

III. OPERATION PHASE

1. Rain water harvesting, as per plan submitted, for roof top run-off and surface run-off should be implemented. Before recharging the surface run-off, pre-treatment must be done to remove suspended matter, oil and grease. The depth of the bore for rainwater recharging should be kept in consultation with DJB/CGWA. No wastewater (such as sewage, trade effluent, backwash of treatment unit, floor washing wastewater etc) should be discharged into the rainwater harvesting structure in order to avoid groundwater contamination.

